



NOTE RE: DATA CABLES
 10NO. IT SOCKETS AS SHOWN TO HAVE
 DATA CABLE RUN TO EACH. CABLES TO
 BE TERMINATED BY OTHERS.

3amp FUSED SPUR
 FOR ALARM SENSOR
 SENSOR FITTED BY OTHERS.
 (IN 4 POSITIONS)

12192

LINKED USING CREAM FACED, FOIL BACKED PLASTERBOARD,
 WITH 100mm INSULATION.
 MONO WHITE CEILING PANELS. WHITE PLASTIC TRIM.
 'BUBBLE WRAP' UNDERFLOOR INSULATION, WITH NON-SLIP
 VINYL OVERLAY.
 4NO. 40' x 8' OPEN PLAN OFFICE UNITS
 LINKED & CAPPED TO CREATE A SINGLE UNIT

TITLE
 40'x8' Linked Units
 Open Plan Offices

Mac Containers

KEY TO SYMBOLS

	Consumer Unit
	2kW Convecter Header
	Twin Skt., 300mm above F.F.L.
	5ft CAT2 Single Fluorescent Light
	Vapour Proof Fluorescent Light
	Light Switch
	External PIR Security Light
	Twin IT Socket *See Note*

FIRE ALARM SYSTEM WILL BE FITTED BY
 A SUPPLIER AND CONNECTED ON SITE.
 (DETAILS TO BE DETERMINED).

STEEL ANGLES TO BE FITTED TO
 SUPPORT A CLIMBING WALL SUPPLIED
 AND FITTED BY CUSTOMER.

ALL INTERNAL PARTITIONING TO BE STEEL
 (FULLY WELDED) WITH PLYWOOD PANELS
 AND INSULATION AS NORMAL.

ALL WINDOWS TO BE ALUMINIUM FRAMED
 DOUBLE GLAZED WITH STEEL SHUTTERS.

EXTERNAL PERSONNEL DOORS TO BE
 STEEL 90° WITH TWO LOOKING BARS.

APPROVAL BOX
 Customer:
 Signature:
 Name:
 Date:

ISSUE	DATE	DESCRIPTION
1	16/10/08	FIRST ISSUE
2	21/11/08	Customer Request: Layout Update
3	25/11/08	Customer Request: Layout Update
4	26/11/08	Customer Request: Layout Update
5	11/12/08	Customer Request: Layout Update
6	06/01/09	Customer Request: Spec. Update

DRAWN	PB	DATE	DRG. No.
		16/10/08	MAC_LX4032V01
			Sheet 1